

PREPARED FOR		PROPOSAL DETAILS	
Griffin McKinzie		Proposal #: PROP-2026-0001	
Southwest Greens		Date: June 08, 2026	
4645 E Cotton Gin Loop, Phoenix AZ 85040		Valid Until: July 08, 2026	
griffin@southwestgreens.com		Prepared By: Jacky Kumar	

PROJECT SUMMARY

Project Name	Backyard Putting Green Installation — Phoenix, AZ	Project Type	Residential / Putting Green
Job Site Address	1234 Desert Vista Drive, Phoenix, AZ 85001	Total Area	1,200 sq ft
Planned Start	July 15, 2026	Planned Completion	July 29, 2026

SCOPE OF WORK

1. Site Preparation	Remove existing vegetation and debris. Grade and compact the sub-base to ensure proper drainage and a level surface.
2. Base Installation	Install decomposed granite base layer (4") compacted to specification. Apply weed barrier fabric over entire area.
3. Artificial Turf Installation	Install premium Southwest Greens synthetic turf — selected product: SWG ProPutt Elite (Nylon/Polyethylene blend). Seam, secure perimeter, and infill with sand/rubber as required.
4. Putting Green Contours	Shape up to 2 custom contour breaks as specified by client. Install cup(s) and flagstick(s) per agreed layout.
5. Edging & Finishing	Install steel or bender board edging around full perimeter. Brush and groom turf to finished presentation standard.
6. Final Inspection & Walkthrough	Complete quality inspection with client present. Address any punch-list items. Obtain client sign-off.

INVESTMENT DETAILS

#	Description	Unit	Qty	Unit Price	Total
1	SWG ProPutt Elite Synthetic Turf (Nylon/PE Blend)	sq ft	1,200	\$6.50	\$7,800.00
2	Decomposed Granite Base Material (4" depth)	ton	8	\$95.00	\$760.00
3	Weed Barrier Fabric	sq ft	1,200	\$0.35	\$420.00
4	Steel Edging / Bender Board	linear ft	140	\$4.50	\$630.00
5	Infill Material (Sand/Crumb Rubber blend)	lb	360	\$1.20	\$432.00

6	Putting Cup Installation (2 cups)	unit	2	\$125.00	\$250.00
7	Labor — Site Prep, Base, Install, Finishing	hrs	48	\$85.00	\$4,080.00
8	Equipment Usage	days	3	\$150.00	\$450.00
9	Permit & Disposal Fees	lump sum	1	\$275.00	\$275.00
Subtotal:					\$15,097.00
Tax (8.6% — Maricopa Co.):					\$1,298.35
TOTAL DUE:					\$16,395.35

PAYMENT SCHEDULE

Milestone	Description	% Due	Amount	Due Date	Status
Deposit	Contract signing & project confirmation	30%	\$4,918.61	Upon Signing	Pending
Material Delivery	Materials delivered to job site	25%	\$4,098.84	July 14, 2026	Pending
Mid-Installation	Base layer & turf installed	25%	\$4,098.84	July 22, 2026	Pending
Final Completion	Final walkthrough & client sign-off	20%	\$3,279.07	July 29, 2026	Pending

TERMS & CONDITIONS

- This proposal is valid for 30 days from the date of issue.
- All work is performed in accordance with applicable Arizona ROC contractor standards.
- Client is responsible for ensuring site access, utilities marking, and HOA approvals prior to start date.
- Southwest Greens warranties all installed turf products for manufacturer's specified warranty period (typically 15 years UV-stabilized, 8-year installation warranty).
- Weather delays may affect the project timeline. Southwest Greens will notify the client of any schedule changes.
- Change orders must be agreed in writing and may affect total project cost and timeline.
- Payment is accepted via ACH, Check, or Credit Card. A 2.75% processing fee applies to credit card payments.

CLIENT ACCEPTANCE	SOUTHWEST GREENS
By signing below, client agrees to the scope, pricing, and terms outlined in this proposal.	Authorized Representative
Signature: _____	Signature: _____
Name: _____	Name: Jacky Kumar
Date: _____	Date: June 08, 2026